

Release: 31/07/2025

DATE	REPORT LINK	PRODUCT	TEST ELEMENT/ASSEMBLY	JOINT/SERVICE SUMMARY	FIRE RESISTANCE LEVEL (FRL)	STANDARD COMPLIANCE	ORIENTATION	REPORT TYPE/NUMBER	
								FIRE TEST	ASSESS-MENT
21/07/2025	15A	FulaFlex FR	75mm thick AAC - aerated concrete wall joints	20mm wide x16mm deep joints at head, perimeter and centre of wall (vertical control joint)	-/90/90**	AS 1530.4 (2014)	Horizontal & Vertical	FP 20542-01	

* See individual test or assessment data for information relating to control Joint configurations, penetrating services and wall/floor thickness.
** See individual test or appraisal data for information relating to FRL's for specific control Joints and service penetrations.
Due to variations in fire rating results using different thicknesses and types of substrates consult fire test reports for specific tested FRL's.